

# Project Portfolio

**SHOTCRETE**

## Tunnels & Shafts

Shotcrete Yard  
Swattenden Lane  
Cranbrook  
Kent, TN17 3PS

Tel: +44 1580 714747  
Email: [enquiries@shotcrete.co.uk](mailto:enquiries@shotcrete.co.uk)  
Website: [www.shotcrete.co.uk](http://www.shotcrete.co.uk)

# SHOTCRETE

---

## TUNNELS AND SHAFTS

**Southern Water Dover**  
**U.K.**

Foul water sewer interceptor tunnel, 1.6km long, “turn key” design and construct sub-contract using NATM technique.  
**value £1.1m**

*Sprayed concrete*

**Chetlain Properties**  
**Thurrock U.K.**

Construction of 2 No. access tunnels at the Dolphin Development, constructed using NATM.  
**value £800,000**

*Sprayed concrete*

**Thames Water Barnet**  
**U.K.**

Design and construction of 25m diameter x 20m deep storm water detention shaft, using our own **Monoshot** design.  
**value £220,000**

*Sprayed concrete*

**London Underground Limited \***  
**London U.K.**

Strengthening of northern line tunnels under River Thames by application of purpose designed sprayed concrete lining.  
**value £213,000**

*Sprayed concrete*

**Railtrack**  
**Bradway, Sheffield U.K.**

Strengthening of brick lined tunnel using a combination of sprayed concrete, anchoring and cementitious grouting.  
**value £420,000**

*Sprayed concrete*

---

**SHOTCRETE**

The sprayed concrete experts

[www.shotcrete.co.uk](http://www.shotcrete.co.uk)

# SHOTCRETE

---

## **Railtrack Rochester U.K.**

Various strengthening and support activities to Higham tunnel, an unlined chalk tunnel, using specialist shotcrete techniques, over a 5 year period.  
**value £270,000**

***Sprayed concrete***

## **Railtrack Strood Tunnel U.K**

Re-profiling and strengthening to sections of Strood tunnel, An unlined chalk tunnel, using special adapted rail mount equipment, During an emergency possession.  
**value £370,000**

***Sprayed concrete***

## **Lend Lease Dartford U.K.**

Twin road tunnels at Blue Water Development, 7.2m in diameter, constructed using NATM, lined with 250mm thick fibre reinforced concrete.  
**value £300,000**

***Sprayed concrete***

## **London Underground Limited \* London U.K.**

Jubilee Line Extension - Strengthening of brick arches with 350mm thick 50 Mpa concrete with microsilica.  
**value £225,000**

***Sprayed concrete***

## **Railtrack London U.K.**

Waterloo Channel Tunnel Terminal -Strengthening of 30 brick arches totalling 12,000m<sup>2</sup>, working from the underside, using overhead sprayed concrete techniques.  
**value £205,000**

***Sprayed concrete***

---

**SHOTCRETE**

The sprayed concrete experts

[www.shotcrete.co.uk](http://www.shotcrete.co.uk)

# SHOTCRETE

---

## Docklands Light Railway London U.K.

Stabilisation of 120 year old brick lined tunnel with 100mm thick fibre reinforced concrete.

**value £213,000**

***Sprayed concrete***

## Scot Rail

### Greenock, Scotland U.K.

Relining of brick built Newton Street Tunnel, using resin anchored steel mesh and sprayed concrete. The lining was completed in 6 weeks, involving placing some 600m<sup>3</sup> concrete.

**value £200,000**

***Sprayed concrete***

## British Airports Authority London U.K.

Heathrow Airport Baggage Tunnel, constructed of six shafts 8m dia. x 16m deep and two chambers 14m dia. x 60m long, using NATM techniques – utilising the wet or shotcrete process primary and secondary lining. Settlement/convergence minimal, well within specified tolerances.

**value £1.05 m**

***Sprayed concrete***

## South West Water Bristol

### U.K.

Lining of sections of drill and blast interceptor sewer to provide temporary support.

**value £300,000**

***Sprayed concrete***

## British Waterways Board Falkirk, Scotland

Design and build of a new 7.0m diameter 170m long canal tunnel Constructed using side drift NATM techniques – utilising wet sprayed Concrete techniques.

**value £1.8m**

***Sprayed concrete***

---

**SHOTCRETE**

The sprayed concrete experts

[www.shotcrete.co.uk](http://www.shotcrete.co.uk)

# SHOTCRETE

---

## **Byera Hill Tunnel**

**Government of St Vincent & Grenadines St  
Vincent, West Indies**

Design and build of an enlargement to an existing 3.0m diameter tunnel to 7.0m diameter 70m long road tunnel.

Constructed on nightly possessions – utilising wet sprayed Concrete techniques.

**value £340,000**

***Sprayed concrete***

## **Park Hill Tunnel**

**Government of St Vincent & Grenadines St  
Vincent, West Indies**

Design and build of an enlargement to an existing 3.0m diameter tunnel to 7.0m diameter 30m long road tunnel.

Constructed – utilising wet sprayed Concrete techniques.

**value £340,000**

***Sprayed concrete***

**Heathrow T5c Back Shunt Tunnel Ferrovial  
Agromen UK Ltd Heathrow.**

Excavation and completion of 30m long x 5.0m diameter tunnel Tunnel constructed using 200mm thick steel fibre reinforced shotcrete primary and secondary linings.

Final finish +/- 5mm floated smooth.

Sprayed using robotic nozzle

**value £600,000**

***Sprayed concrete***

---

**SHOTCRETE**

The sprayed concrete experts

[www.shotcrete.co.uk](http://www.shotcrete.co.uk)